# Smartalock

Smartalock L2 Installation Guide - Predrilled

What you need:

Lock (1 per door)
Wire Cover (1 per door)
Latch (1 per door)
RJ45 Cable (1 per door)
4x40mm Lock screws (3 per door)
4x30mm Wirecover screw (1 per door)
3x16mm Latch Screws (2 per door)

Power Screwdriver
Site Specific Cabling Plan

1

Smartalock12 Hub

Predrilled holes

Run cable from the Smartalock12 hub in the toekick space to the correct locker as specified in the Site Specific Cabling Plan. THIS MUST BE DONE FIRST to avoid locking the door before the lock has power.

2

Align the lock with the predrilled holes in the locker wall. Insert the 2 lock screws through the slotted bosses and fasten. These slots will allow you to fine tune the locks positioning later. CONNECT THE CABLE NOW

3

Predrilled holes

THIS WAY UP

Align the latch with the predrilled holes on the inside of the door and fix using the provided screws as shown.

4

Ensure controller system is correctly installed and powered on (see guide at http://support.smartalock.com/support/solutions/articles/5000857160-smartalocklite-l2-controller-cabling-guides). Shut the doors until the latch catches. Open lock via unlock switch on the smartalock12 Hub. Slightly loosen the screws and slide the lock forwards or backwards as required and re-tighten.

5

Once lock is in the correct position secure in place with the third screw.

6

Capping

Wire Cover

Fit the aluminium extrusion capping if appropriate. Press the wire cover into place and fasten with 25mm wood screw. This locker is now complete. Repeat process for all lockers